

KANSAS DRILLERS LOG


API No. 15 — NA — County Number

S. 34 T. 34S R. 32 W

Loc. 330' FS & E lines

County Seward

640 Acres
N



Locate well correctly

Elev.: Gr. _____

DF 2771 KB _____

Operator

Diamond Shamrock Corporation

Address

P O Box 631

Well No.

1

Lease Name

L.H. Fincher et ux "A"

Footage Location

330 feet from (X) (S) line 330 feet from (E) (W) line

Principal Contractor

Shamrock Rotary #1

Geologist

Spud Date

07-29-55

Total Depth

6143

P.B.T.D.

Date Completed

09-11-55

Oil Purchaser

Panhandle Eastern

CASING RECORD

Report of all strings set— surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	17"	13 3/8		718	Pozmix	600	
Intermediate	12 1/4	9 5/8	36	2656	Pozmix	800	
Production	7 7/8	5 1/2	15.5	5987	Pozmix	250	

LINER RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			6		5930-5948
TUBING RECORD					
Size	Setting depth	Packer set at			
2 7/8	5953	-			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acidized w/500 gal mud acid. Fraced w/10,000 gal petrogel	5930-5948
and 7000# sand.	

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)				
05-10-56	flowing				
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	11.90 bbls.	2446 MCF	0 bbls.	205,546	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		
Sold			5930-5948		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on an open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Diamond Shamrock Corporation		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 1	Lease Name L.H. Fincher et ux "A"	
S 34 T 34SR 32 W		

WELL LOG			SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.				
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
			Dolomite	2642
			Lansing	4595
			Cherokee	5415
			Atoka	5689
			Morrow	5885
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.				

Date Received	 Signature Manager of Drlg & Prod Operations Mid- Time Continent Division September 27, 1979 Date
---------------	--