

11-241
MAP NO. K-84

ELEV. 2747DF 2750KB

STATE Kans COUNTY Seward SEC. 13 TWP. 34S RGE. 32W

OPERATOR Anadarko Prod. & Falcon Seaboard Drlg. LOC. C SE NW

WELL NO. 1 FARM NAME Robt. Davies "B" FT. FROM _____ LINE _____

Unnamed Pool (conf) FT. FROM _____ LINE _____


FR. 9/27/61 SPUD 9/29/61 COMP. 11/24/61

CONT./GEOL. Herndon Drlg. Tools

COMPLETION RECORD

NAME PRODUCING INTERVAL FROM - TO PERF. W/HOLES TREATMENT RECORD

a	_____	_____	_____	_____
b	_____	_____	_____	_____
c	_____	_____	_____	_____
d	_____	_____	_____	_____



d I. P. OIL/DIST. _____ WTR. _____ GAS _____ M.C.F.P.D. _____ CHK. _____ HRS. _____

b " " " " " "

c " " " " " "

d _____

D & A

D & A ()

SIP# _____ FI TP # _____ FI CP# _____ SIBHP _____

GOR. _____ GR. _____ PBTD _____ TD 6612

CASING - CEMENT RECORD

SIZE	DEPTH	W/SAX.	SIZE	DEPTH	W/SAX.
<u>8-5/8"</u>	<u>2617</u>	<u>400</u>			
<u>4 1/2"</u>	<u>4704</u>	<u>250</u>			

OPERATOR Anadarko & Falcon Seaboard WELL NO. 1 Robt. Davies "B" ELEV. 2750 KB

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
-------------	-------	---------	------------	-------	---------

KB Elev Tops & Datum

RTD (St L) 6610			Herr	2664	+ 86
			U Kri	2691	+ 59
			Winf	2778	- 28
DST #1 (Morr) 5935-81			CG	3060	- 310
Op 1 hr., R 10' M,			Tor	4411	-1661
IBHP 107#/30", IFP 26#,			Lans	4540	-1790
FFP 53#, FBHP 53#/45"			Marm	5247	-2497
DST #2 (Chest) 5980-6040,			Cher	5397	-2647
Op 2 hrs, R 30' M,			Morr	5791	-3041
IBHP 357#/30", IFP 115#,			Morr sd	5947	-3197
FFP 125#, FBHP 260#/45"			Chest	5971	-3221
RTD 6610, Ran log,			St Gen	6266	-3516
WLT #1 (St L) 6422-24 1/2,			St L	6371	-3621
Op 10", R 20,800 cc			LTD	6612	-3862
wtr (3% SW) IBHP 2125#/10"					
DST #3 (St L) 6570-6610, Op 1 hr., R 180' WM, IBHP 2103#/ 30", IFP 63#, FFP 105#, FBHP 1803#/45"					
WLT #2 (Lans) 4551-53 1/2, Op 75", R .95 cfg + 800 cc Oil + 20,000 cc wtr, IBHP 1600#/15", FBHP 1280#/22"					

Anadarko took over on 10/27/61, at this point, 4½" @ 4704
w/250, 8/4551-53 (Lans) Swb 3 GW + scum oil/2 hrs, 250 A,
swb 216 GF, 60% wtr, 40% oil/NT, Clor 73,248 ppm, 1500 A
swb 3 3/4 BO + 2 3/4 BFW, las 6 hrs, of 32 hr tst,
PB 4200, 16/4145-49 (Shawnee), 500 A, swb 3 GAWPH, NS, NT
(No Shawnee called) D & A COMPLETE

LIBERAL ELECTRIC LOG TOPS

2751 KB

Winfield 2780 (+29)
Council Grove 3022 (-271)
Heebner 4385 (-1634)
Toronto 4410 (-1659) \$ AWPB (Shawnee)
Lansing 4538 (-1787) \$ 3 3/4 BO + 2 3/4 BW/6 hrs.
Marmaton 5246 (-2495)
Morrow 5798 (-3047)
"S-3" 5947 (-3196) 3/4; tst mud
Chester 5968 (-3217) tst mud
Ste. Gen 6264 (-3513)
St. Louis 6416 (-3655) WLT Filt + XW
TD 6610 D & A