

WILDCAT

12-278 W Map No. 84

OPER ANADARKO PRODUCTION CO.

LIBERAL, KANSAS


WELL #1 REIMER "C"

CONTR. LOHMANN-JOHNSON

WC 1 MI S/ARKALON FIELD (MRW-MISS)

I.P. D&A

API #15-175-20044



S-T-R 10-34S-32W

SPOT C SE NW

CO SEWARD, KS

ELEV. 2760 GR

*22767DF*

SPUD 12-1-68 8 5/8" 1577/725 SX

DST 1 (MRW ) 5712-5940, OP 10 MIN, WB, OP 40 MIN, REC 115' MUD, ISIP 88#/40 MIN, PRE FLOW 88-88#, FP 92-92#, FSIP 112#/40 MIN, HP 2680-2591#

DST 2 (STL) 6266-6466, OP 40 MIN, REC 100' MUD, ISIP 1901#/40 MIN, FP 46-51#, FSIP 1480#/40 MIN, HP 2991-2924#

DST 3 (MAR) 5180-5226 (STRAD PKR), OP 40 MIN, REC 365' SLI WCM, ISIP 1701#/40 MIN, FP 66-198#, FSIP 1546#/40 MIN HP 2475-2457#

DST 4 (LAN) 4770-4828 FAIL

DST 5 (LAN) 4814-4832, (STRAD PKR), OP 30 MIN, REC 270 WCM + 530 WTR, ISIP 1560#/40 MIN, FP 240-356#, FSIP 1560#/40 MIN, HP 2237-2226#

D 6466 LOG D&A COMPLETED 12-23-68

GR LOG TOPS

TOR 4384-1624

LAN 4509-1749

MAR 5213-2453

MRW 5764-3004

CHEST 5923-3163

ST L (PORO)

6406-3646

ST GEN 6456-3696

LTD 6466-3706

TD IN ST GEN FORM

COMP ISSUED 12-27-68