


9-310W MAP NO. 84 SEC. 5-34S-32W
 STATE Kans COUNTY Seward LOC C SW NE
 OPER. Anadarko Production Co. - Box 351 - Liberal, Ks FT/FR _____ LINE _____
 WELL 1 FARM Light "D" FT/FR _____ LINE _____
 WELL Arkalon West Ext ELEV 2786 P-S GR 2796 D 2799 KB _____
 CONT. E.F. Wakefield GEOL. John Kimberly
 CO. INT. 6200' Miss Test
 F.R. 9-1-64 SPUD 9-4-64 COMP. 9-29-64
 TD. 6265 FM. St Gen PBTD. _____



COMP. RECORD

D&A

Data Inc.

8 5/8" @1605 w/800 sx.

(GR Log)	Mrw	5708	-2922
Kri 2654 / 132	L/" 1m	5862	-3076
Winf 2742 / 44	B/" "	5880	-3094
CG 3025 - 239	L/Mr sd	5900	-3114
Wab not picked	B/" "	5915	-3129
Tor 4370 -1584	Chest	5915	-3129
Lans 4503 -1717	St G	6224	-3438
	LTD	6262	-3476

ST #1 (L/Mrw) 5682-5924, Op 40", R 50' M, ISIP 401#/45", IFP 31#, FFP 31#, FSIP 216#/45", RTD 6265 (St Gen), Ran Log,

PGAC Log,
 WLT #1 (Tor) (Two chamber tool) 4527-29½, Op 60", Op 30", 1st chamber, R 4100 cc filt wtr, 2nd chamber R 1650 cc filt wtr, No ISIP taken, SP 50 & 50W, FSIP 1200#/17"
 WLT #2 (Mrw) 5875½-78, Op 1 hr, R 1050 cc filt wtr, ISIP 2300#/100#, SP less than 50#, FSIP less than 50#/10"
 WLT #3 (Wab) 3545-47½, Pkr Failed
 WLT #4 (Wab) 3545-46, Op 1 hr, R 1600 cc filt wtr, ISIP 945#/20", SP less than 100#, FSIP less than 100#/20"
 D&A - COMPLETED (9-22-64)

LIBERAL ELECTRIC LOG TOPS

2786 GL

Winfield 2744 (+42)
Heebner 4344 (-1558)
Toronto 4370 (-1584)
Lansing 4504 (-1718) WLT filt wtr
Marmaton 5068 (-2382) 2382
Morrow 5708 (-2922)
"S-3" (Im) 5860 (-3074) 4/26/WLT/filt wtr /
"S-3" Sand 5900 (-3114) 4/16 /DST Mud
Chester 5916 (-3130)
Ste. Gen 6236 (-3450)
TD 6262 D & A

5068
2782
2382