


2-38W MAP NO. _____ REPL. COMP. SEC. 31-34S-32W
 STATE Kans COUNTY Seward LOC App C NE SW
 OPER. Whitestone Pet., Corp., Dallas, Texas 1980 FT/FR W LINE
 WELL 1 FARM L.G. Blackmer 2330 FT/FR S LINE
Three Star Extension ELEV. 2769 GR. 2779 DF 2781 KB
 CONT. Co., tools GEOL. _____
 CO. INT. 6800' Oil & Gas Test
 F.R. 10-22-62 SPUD 12-10-62 COMP. 2-5-63
 TD. 6710 FM. Mississippian PBT. 6100
 8 5/8" @2290/700 sx. - 4 1/2" @6265/275 sx.
 Morr 6025-38 - 52 - 500A + Frac, AOF 5,800 Mcfgpd
 + 1 3/4 BSW/scum oil/4 hrs, SIP 1591#, SCP 1324# *Data Inc.*



COMP RECORD

FTP 1246#

(KB Log)

Tor	4387	-1606	Lo Morr sd	6022-43	-3241
Lans	4534	-1753	Miss	6070	-3289
Morr	5826	-3045	LTD	6710	-3929

RTD 6710, Log

WLT #1 (Miss) 6167 1/2-70, No Rec

WLT #2 (Lo Morr) 6034-36 1/2, Op 90", R 9.03 Cfg + 2400 cc Filt

wtr, IBHP 2150#/30", No FP's, FBHP 2150#/20"

WLT #3 (Lans) 5032-34 1/2, Op 90", R 12,000 cc Filt wtr, IBHP 1425#/20", No FP's, FBHP 1425#/20"

WLT #4 (Waub) 3614-16 1/2, Op 90", R 1200 cc Filt wtr, IBHP 0#/20", No FP's, FBHP 200#/30", 4 1/2" 6265/275 sx.,

Perf 44/6164-75, 28/6178-85 (Miss) 500A Ga 100 Mcfgpd/12 hrs, SIP 1350#/12 hrs, 15,000A Flow ld, Ga 100 Mcfgpd, Ga 200 Mcfgpd thru 3/4" ck, PB 6100 PBT, Perf 52/6025-38 (Morr) 500A, Est Ga 1000 Mcfgpd thru 3/4" ck, Frac (15,000 GA + 15000# sd) Ga 5,000 Mcfgpd thru 16/64" ck, FCP 1400#, FTP 1300#, 5 pt AOF 5800 Mcfgpd + 1 3/4 BSW/ scum oil/4 hrs, SIP 1591#, FCP 1324#, FTP 1246#, Cal Delvi 2850 Mcfgpd, Morr 6025-38 COMPLETED (1-28-63)

REPLACEMENT COMPLETION: (2-26-63)
 CORRECTION Was 2847 KB, Is 2781 KB

LIBERAL ELECTRIC LOG TOPS

2781 KB

Winfield 2742 (+39)
Heebner 4362 (-1581)
Toronto 4386 (-1605)
Lansing 4534 (-1753) WLT Filt wtr
Marmaton 5248 (-2467)
Morrow 5827 (-3046)
"S-3" 6022 (-3241) 4/20; ϕ 5,800 MCF
Chester 6042 (-3261)
Ste. Gen 6406 (-3625)
St. Louis 6580 (-3799)
TD 6710