

7-301W Map No. K-84
OPER ANADARKO PROD CO. - Liberal, Ks.



S-T-R 19-34S-32W

SPOT App C SW NW

CO SEWARD (Ks)

ELEV 2811 GR

WELL #1 ETZENHAUSER "A"

WTR Moran Drlg.

FIELD Condit Field Ext (Multi Pay O&G)

I.P. P 170 BOPD & tr wtr, Gr 39.6 deg., from

Chest Pfs 6284-92

(Gr Logs:)

Win	2758	/	53
CG	3026	-	215
Tor	4374	-	1563
Lans	4508	-	1697
Mrw	5792	-	2981
Mrw sd	5958	-	3147
B/" "	5982	-	3171
Chest	5984	-	3173
Chest sd			
	6272	-	3461
B/" "	6310	-	3499
St Gen	6374	-	3563
LTD	6400	-	3589

16/6284-92 (Chest) § 15½ BO w/GSG
NT (Nat) 500A, § & Flo 62 BO - 3-3/4 hrs, 2-3/8" tbg,
6305, Flo 38 BO / 1,020,000 CFGPD, NT, CO Flow test
247 BOPD, 20/64" ck, FCP 700#, FTP 250#, -
State Pot: P 170 BOPD / tr W, Gr 39.6 deg, Ches Pfs 6284
92 - COMPLETED on 7-28-65

Data Inc

MISC DATA

GEO: Bob Posey

FTG

SUPPT

CSG 8" @1600 w/700 sx. 4" @6399 w/125 sx.

ELEV 2820 DF

2823 KB

SPUD DATE 4-11-65

DRLG COMP

FR by DATA 4-12-65

COMP by " 7-29-65

LS 2823DF

LIBERAL ELECTRIC LOG TOPS

2814 GL

Winfield 2758 (+56)

Heebner 4352 (-1538)

Toronto 4374 (-1560)

Lansing 4508 (-1694)

Marmaton 5202 (-2398)

Morrow 5784 (-2970)

"S-3" Sand 5958 (-3144) 10/24

Chester 5982 (-3168) Sand

Sand 6272 (-3458) 14/30; ϕ 170 BOPD w/tr wtr

TD 6400