


A-5-194

MAP NO. _____ ELEV. 1807 DF
 STATE Kansas COUNTY Clark SEC. 32 Twp 34 S Rge 21 W
 OPERATOR Sinclair Oil & Gas Company LOC. C SW NE
 WELL NO. 1 FARM NAME Bentley Randall Jr. FT. FROM _____ LINE
 POOL Snake Creek (PD 3600) FT. FROM _____ LINE
 FR. 3-28-61 SPUD 3-28-61 COMP. 5-9-61

CONT./GEOL. Barbour tools

NAME PRODUCING INTERVAL	COMPLETION RECORD		TREATMENT RECORD
	FROM - TO	PERF. W/HOLES	
a. <u>Morrow</u>	<u>5448-5508</u>	<u>173</u>	<u>750 A-F/45X45</u>
b. _____	_____	_____	_____
c. _____	_____	_____	_____
d. _____	_____	_____	_____



d. I. P. OIL/DIST. 8 BCPD WTR. _____ GAS 10,500 M.C.F.P.D. _____ CHK. 3/4" HRS. 24
 b. " " " " " "
 c. " " " " " "

d. SICP 1600

D & A ()

SIP# _____ FI TP # 800 FI CPH _____ SIBHP _____
 GOR. _____ GR. 60° PBDT 5510 TD 5680

SIZE	DEPTH	CASING - CEMENT RECORD W/SAX.	SIZE	DEPTH	W/SAX.
<u>30"</u>	<u>24</u>	<u>cem</u>	<u>5 1/2"</u>	<u>5620</u>	<u>200</u>
<u>10-3/4"</u>	<u>600</u>	<u>600</u>			

OPERATOR Sinclair O & G WELL NO. 1 Bentley Randall Jr. ELEV. 1807 DF

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
Heebner	4262		Heebner	4258	
Toronto	4301		Toronto	4297	
Lansing	4479		Lansing	4475	
Marmaton	5115		Marmaton	5109	
Cherokee	5264		Cherokee	5250	
Morrow	5410		Morrow	5405	
Morrow Sand	5460		Upper Morrow Sand	5454	
Mississippian	5539		Lower Morrow Sand	5471	
			Chester	5526	
			Ste Genevieve	5620	
			St Louis	5626	

Spud 3-28-61, w/spudder. 30" @ 24 w/cem. 10-3/4" @ 600 w/600 sx.

DST # 1 (Morr) 5438-82, op 15 mins, GTS 2 mins, SI 1 hr, op 60 mins, ga 550 MCF/15 mins, ga 6100 MCF/30 mins, ga 6200 MCF/45 mins, ga 6200 MCF/60 mins, rec 15' dist, gty 60°, ISIP 1842/60 mins, FP 1585-1585, FSIP 1844/60 mins.

DST # 2 (Morr) 5490-5520, op 1 hr, wk blo 7 mins-died, rec 10' M, ISIP 301/60 mins, FP 102-112, FSIP 112/60 mins.

RTD 5680, logs. 5 1/2" @ 5620 w/200 sx. MICT. CO to 5555.

SHEET NO. 2

MAP NO. _____

STATE Kansas COUNTY Clark SEC. 32Twp 34 S Rge 21WOPERATOR Sinclair O & G LOC. C SW NEWELL NO. 1 FARM NAME Bentley Randall Jr.

P/72/5490-5508. Swb 102 BL/8 hrs. Swb dry/NS. Trt w/42 gal
Kem Zone w/SG/12 hrs. Frac 15,000 gel Ac X 15,000 sd. Flod
48 BLPH/4 hrs. Ga 4000 MCF, 3/4" ck, FTP 450, FCP 350.

P/33/5471-80 Frac 10,000 gel Ac X 10,000 sd. Flod 30 BLPH/3
hrs. Ga 5100 MCF, 3/4" ck, TP 750, CP 1400. Ga 8800 MCF +
184 BL, 3/4" ck, FTP 750, FCP 1400. Flush w/750 gel Ac, on
perf 5471-5508.

P/68/5448-64 Frac 20,000 gel Ac X 20,000 sd, w/40 sealer balls
Swb & flod 225 BL/10 hrs, ga 4400 MCF, 3/4" ck, FTP 600, FCP
300. CO to 5510.

IP ga 10,500 MCF + 8 BCPD + 264 BL/24 hrs, gty 60°, 3/4" ck,
FTP 800, SICP 1600 from Morrow (5448-5508).

COMPLETE 5-9-61

OPERATOR

WELL NO.