

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Seward

County. Sec. 6 Twp. 34S Rge. 33 ~~W2E~~ (W)

Location as "NE/CNWxSWx" or footage from lines 1980' FNL, 1320' FEL of NE/4

Lease Owner Cities Service Oil Company

Lease Name Fincham A Well No. 2

Office Address 3545 N. W. 58th Street, Okla. City, Okla. 73112

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 9-11 19 76

Application for plugging filed 9-11 19 76

Application for plugging approved 9-11 19 76

Plugging commenced 9-11 19 76

Plugging completed 9-16 19 76

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production N/A 19     

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas

Producing formation N/A Depth to top N/A Bottom N/A Total Depth of Well 6420 Feet

how depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
N/A	---	----	----	Surface csg 8-5/8"	1604'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

9-11-76 to 9-16-76: Spotted cement plugs as follows:

50 sx 6250-6400 Chester

70 sx 2550-2750' Hugoton

35 sx 1553-1663' Btm Sp.

10 sx 4' - 35'

5 sx Rat hole

5 sx Mouse hole

Cut off 8-5/8" csg 4' below GL, at which point a steel cap with well name and date was welded on.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lohman Johnson Drilling Company, Inc.

Address 1302 Old National Bank Building, Evansville, Indiana 47708