


WELL RECORD

(Mail to Kansas Geological Survey, 4150 Monroe Street, Wichita, Kansas 67209)



Lease Name: Fincham A Well No. 2  
 Well Located: 1980' FNL, 1320' FEL of NE/4  
SEC 6 TWP 34S R23W 33W  
 Operator: Cities Service Oil Company  
 Address: 3545 N. W. 58th, Oklahoma City, Okla. 73112  
 Elevation: Ground 2858' D.P. 2866' K.B. 2867'  
 Type Well: (Oil, gas, dry hole) Dry Hole

Drilling Commenced: 8/24/76 19 Drilling Completed: 9-11 1976  
 Well Completed: 9/16/76 19 Total Depth 6420'  
 Initial Production: Dry Hole

Casing Record

Size: 8-5/8" Set at 1604' Size: ---- Set at ----  
 Size: ---- Set at ---- Size: ---- Set at ----

Liner Record

Size: ----- Set from ----- To -----

Cementing

Casing Size	Sacks	Type Cement and Additives
<u>8-5/8"</u>	<u>650</u>	<u>Class H. Cemented w/700 sx. w/3% CaCl. Cement circulated: 50 sx.</u>
<u>-----</u>	<u>-----</u>	<u>-----</u>
<u>-----</u>	<u>-----</u>	<u>-----</u>

Perforations

Formation	Perforated Interval and Number Shots
<u>N/A</u>	<u>N/A</u>
<u>-----</u>	<u>-----</u>
<u>-----</u>	<u>-----</u>

Electric Log Run. (Show type log and depths covered)

Ran Schlumberger Dual Induction Laterolog & Compensated Formation Density w/GR-Caliper Log to 6418'

(Fill in formation and related information on reverse side)

STATE OF KANSAS  
STATE CORPORATION COMMISSION - CONSERVATION DIVISION  
3830 South Meridian - Box 17027  
Wichita, Kansas 67217

FORM C-2

DATA AND AFFIDAVIT

(On Cementing in Surface or Drive Pipe and required by Rule 82-2-123 of the Commission for compliance with Section 55-136, 55-137 and 55-138, 1947 Supplement to G. S. Kansas 1935)

LEASE OWNER Cities Service Oil Company

OFFICE ADDRESS 3545 N. W. 58th Street, Oklahoma City, Okla. 73112

LEASE NAME Fincham A WELL NO. 2 COUNTY Seward

EXACT SPOT LOCATION 1980' FNL, 1320' FEL of NE/4SEC. 6 TWP. 34S RGE. 33 (W) (E)

CONTRACTOR Lohmann-Johnson Drilling Company

OFFICE ADDRESS 1320 Old National Bank Building, Evansville, Indiana 47708

Drilled with ~~(Cable)~~ (Rotary) tools: Date pipe set 8/25/76

SURFACE HOLE DATA

SURFACE PIPE DATA

Size of Hole 12-1/4" Csg. (new) ~~size~~ Size 8-5/8" wt. 24#

Depth 1605' Where set 1604'

METHOD OF CEMENTING Class H. 650 sx. Cemented w/700 sx w/3% CaCl. Cement circulated: 50 sx.

Cement: Amount and kind \_\_\_\_\_

Method: (By Service Co., Dump, Tog., etc.) Service Company

Est. Height Cement behind pipe Surface

GROUND WATER INFORMATION

Depth to bottom of lowest fresh water producing stratum 600'

Name of lowest fresh water producing stratum Ogallala

Surface elevation of well 2858'

ADDITIONAL INFORMATION

(Additional information may be submitted on separate sheet)

A F F I D A V I T

STATE OF OKLAHOMA, COUNTY OF OKLAHOMA SS,

I, H. E. Massey, of the Cities Service Oil Company, being first duly sworn on oath, state: That I have knowledge of the facts, statements and matters herein contained and that the same are true and correct.