

2-34-33W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- ANADARKO PRODUCTION
Farm- Gilmore "B" No.1

SEC. 2 T. 34 R. 33W
C SW NE
660' N of SL, 660' E of WL

Total Depth. 6603

Comm2-17-65

Comp. 3-7-65

County Seward


KANSAS

Shot or Treated. Lower Chester 6169'-6170' 4 shots, Lower Chester 6181-6191'

Contractor. Moran Bros.

20 Shots

Issued. 5-8-65



CASING:

8 5/8" 1603' 850 sx/
4 1/2" 6270' 150 sx.

Elevation. 2835.16' GL

Production. 6600MCFGPD

Figures Indicate Bottom of Formations.

surface sand & red bed	700
red bed, gypsum & sand	1265
" " " & Anhydrite	1604
red bed & gypsum	2073
red bed & shale	2358'
shale & lime	2638
shale & anhydrite	2835
shale & lime	4288
lime	5482
lime & shale	6208
lime	6600
TD	6603

TOPS: Scout

Herington	2616
Upper Krider	2636
Lower Krider	2668
Winfield	2734
Upper Fort Riley	2792
Council Grove	2990
Toronto	4326
Lansing	4455
Morrow	5722
Lower Morrow Sand	5874-98
Chester	5898
Lower Chester Sand	6176-94
St. Genevia	6262
St. Louis	6354
Spergen	6508