

5-34-33W

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY CITIES SERVICE OIL CO.

FARM Anthony "A"

NO. 1

SEC. 5 T. 34 R. 33W

LOC. SE SE SE NW

100' N. & 100' W. of Center

TOTAL DEPTH 2785

COMM. 6-15-50

COMP. 6-22-50


SHOT OR TREATED

CONTRACTOR Barbour Drlg. Co.

ISSUED 6-16-51

COUNTY Seward

KANSAS



CASING

8 5/8" 640' cem. w/325 sx
 5 1/2" 2784' cem. w/700 sx

ELEVATION 2878

PRODUCTION 5,010,000 gas

FIGURES INDICATE BOTTOM OF FORMATIONS

sand & clay	615
red bed	975
shale & lime	1550
sandy shale & shells	1800
shale & lime	2030
lime	2165
shale & lime	2585
lime	2785
Total Depth	

Tops:	
Herington	2638
Upper Krider	2660
Lower Krider	2690
Winfield	2747

Perf:
 40 shots 2636-44
 40 " 2660-68
 150 " 2692-2722
 20 " 2728-32
 30 " 2746-52
 40 " 2756-64
 70 " 2692-2706
 56 jet shots 2699-2706

S.I.P. 416.7#