

7-34-33W

## KANSAS WELL LOG BUREAU---KANSAS GEOLOGICAL SOCIETY

505 EAST MURDOCK - WICHITA, KANSAS

COMPANY CABOT CARBON COMPANY

SEC. 7 T. 34 R. 33W

FARM Metcalf

NO. 1

LOG. NE NE SW

TOTAL DEPTH 2722

COMM. 10-9-50

COMP. 10-28-50


SHOT OR TREATED Acid: 16,000

CONTRACTOR

ISSUED 2-10-51

COUNTY Seward

KANSAS



## CASING

10 3/4" 591' cem. w/300 sx

7" 2612' cem. w/750 sx

5 1/2" liner 125'

ELEVATION

2873

I.P.A.

PRODUCTION 12,464,000 gas

FIGURES INDICATE BOTTOM OF FORMATIONS

|                   |      |
|-------------------|------|
| sand, clay        | 100  |
| clay, shells      | 200  |
| sand, gravel      | 280  |
| sand, clay        | 580  |
| red beds          | 600  |
| red beds, gyp     | 890  |
| gyp               | 1060 |
| red bed, shells   | 1400 |
| red rock, anhy.   | 1629 |
| red rock, shale,  |      |
| lime              | 1790 |
| anhydrite         | 1935 |
| shale, anhydrite  | 2020 |
| red rock, shale   | 2155 |
| shale, anhydrite  | 2455 |
| anhydrite, shale, |      |
| lime              | 2545 |
| shale, anhydrite  | 2580 |
| anhydrite, lime   | 2630 |
| lime              | 2721 |
| shale             | 2722 |

Total Depth 2722

Scout Top:

Herington 2615

S/G 2678-82

Inc. 2695-2715

*Tops:*  
*Herr* 2615  
*Upper Tri* 2646  
*Lower Tri* 2670