

8-34-33W

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY CITIES SERVICE OIL CO.

SEC. 8 T. 34 R. 33W

FARM Fitzgerald NO. 1

LOC. SE SE SE NW
100' N. & 100' W. of Center

TOTAL DEPTH 2800

COMM. 6-23-50

COMP. 6-30-50


SHOT OR TREATED

CONTRACTOR Barbour Drlg. Co.

ISSUED 6-16-51

COUNTY Seward

KANSAS



CASING

8 5/8" 640' cem. w/325 sx
5 1/2" 2799' cem. w/700 sx

ELEVATION 2887

PRODUCTION 8,000,000 gas

FIGURES INDICATE BOTTOM OF FORMATIONS

sand & clay	570
red bed	920
sand & shale	1150
shale & shells	1600
anhydrite & shale & lime	1670
sand, shale & lime	1810
shale & lime	2525
lime	2585
lime & shale	2655
lime	2800
Total Depth	

Tops:

Herington	2642
Upper Krider	2667
Lower Krider	2698
Winfield	2753

Perf:

40 shots	2642-50
40 "	2668-76
150 "	2696-2726
100 "	2754-74

S.I.P. 421.4#