

12-34-33W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- ANADARKO PRODUCTION
Farm- Worthington "A" No. 1

SEC. 12 T. 34 R. 33W
C NE SW
1980' N of SL 1980' E of WL

Total Depth. 6384'
Comm. 4-13-64 Comp. 4-30-64
Shot or Treated. 6255-69 28 shots 1000 gal 10,000 gelled diesel
Contractor. Moran Bros.
Issued. 7-18-64

County Seward
 KANSAS



CASING:

8 5/8" 1599' cem w/ 850 sx
5 1/2" 6380' cem w/310 sx

Elevation. 2830.44 GL

Production. 11,600,000 CFG

Figures Indicate Bottom of Formations.

sand	675
red bed	1030
red bed & anhydrite	1651
red bed & sand	2366
anhydrite, lime & shale	2557
lime & shale	5992
lime	6179
lime & shale	6384 RTD
Total Depth	

TOPS: SCOUT	
Council Grove	3028
Toronto	4357
Lansing	4499
Morrow	5793
Mississippi	5990
St. Genevieve	6347