

13-34-33W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company ANADARKO PRODUCTION
Farm- Eubank "B" No 2

SEC. 13

T. 34 R. 33W
C NE NE

Total Depth. 6376

Comm. 1-12-65


Comp. 1-29-65

Shot or Treated. Chester 6276'-6280' 8 shpts 500 ga; acid

Contractor. Moran Bros.

Issued. 4-10-65

County Seward
KANSAS



Elevation. 2821.71' GL

Production. 153 BOPD, 293 MCFGPD

CASING:

3 5/8" 1609' 850 sx.
4 1/2" 6375' 210 sx.

Figures Indicate Bottom of Formations.

sand & clay	620
red bed, gypsum & sand	1340
red bed & gypsum	1614
anhydrite & red bed	2114
anhydrite & shale	2737
shale & lime	3067
lime	3722
shale & lime	4662
lime	5432
shale & lime	6238
lime	6376
TD	6376

TOPS: Sxout

Krider	2667
Winfield	2762
Toronto	4350
Lansing	4489
Morrow	5766
Lower Morrow Sand	5957-66
Chester	6033
Morrow Chester	6266-86
St. Genevia	6333

13-34-33W

DRILLER'S LOG

WELL NAME: Kubank "B" No. 2; COMPANY OPERATING: Anadarko Production Company
 ADDRESS of COMPANY: P. O. Box 351, Liberal, Kansas
 WELL LOCATION: C 1/4 NE 1/4 NE 1/4,
630 ft. NORTH of south line; south of north line
709 ft. EAST of west line; Sec. 13, Twp. 34N, Rge. 33W, Seward County, Kansas
 DRILLING STARTED 1-12, 1965; DRILLING COMPLETED 1-29, 1965
 WELL COMPLETED 2-3, 1965; WELL CONNECTED _____, 19____
 ELEVATION: 2821.71 ft. Ground Level; CHARACTER OF WELL (Oil, Gas, or Dry Hole) Oil

OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION					
Name	From	To	No. of Shots	Gallons Used	Kind Used
Chester	6276	6280	8	500	15% NE

CASING RECORD

Size	Amount Set	Sacks of Cement	Amount Pulled
8-5/8"	1609'	850	
4-1/2"	6375'	210	

FORMATION RECORD

Formation	Top	Bottom	Formation	Top	Bottom
Sand & clay	0	620			
Red bed, Gypsum & sand	620	1340			
Red bed & gypsum	1340	1614			
Anhydrite & red bed	1614	2144			
Anhydrite & shale	2144	2737			
Shale & lime	2737	3067			
Lime	3067	3722			
Shale & lime	3722	4662			
Lime	4662	5432			
Shale & lime	5432	6238			
Lime	6238	6376			
Total Depth	6376				

RESULTS of INITIAL PRODUCTION TEST: Swabbed & flowed 250.07 bbls. in 22-1/2 hours.