

15-34-33W


WELL LOG BUREAU-- KANSAS GEOLOGICAL SOCIETY
508 East Murdock Wichita, Kansas

Company - CITIES SERVICE OIL CO.
Farm - Eubank "D" No. 1

SEC. 15 T. 34 R. 33W
NE NE NE SW
100' S & 100' W. of Center

Total Depth. 2750
Comm. 9-19-50 Comp. 9-25-50
Shot or Treated.
Contractor. Barbour Drlg. Co.
Rosed. 6-23-51

County. Seward
KANSAS



CASING:

8 5/8" 640' cem. w/300 sx
5 1/2" 2749' cem. w/700 sx

Elevation. 2832
2834 (end.)

Production. 4,090,000 gas

Figures Indicate Bottom of Formations.

sand & clay	595
red bed	790
shale & shells	1550
lime	1720
shale	1875
shale & lime	2295
anhydrite & shale	2485
lime	2750
Total Depth	

Tops:	
Herington	2588
Upper Krider	2612
Lower Krider	2650
Winfield	2706

perf:
60 shots 2596-2606
80 shots 2622-30
150 shots 2650-80

S.I.P. 431.8#