

17-34-33W


WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
508 East Murdock Wichita, Kansas

Company - CITIES SERVICE OIL CO.
Farm - Brown "C" No. 1

SEC. 17 T. 34 R. 33W
NE NE NE SW
100' S. & 100' W. of Center

Total Depth. 2780
Comm. 9-12-50 Comp. 9-18-50
Shut in Treated.
Contractor. Barbour Drilling Co.
Issued. 6-23-51

County. Seward KANSAS



CASING:

8 5/8" 680' cem. w/275 sx

Elevation. 2875
2876 (md)

Production. 11,300,000 gas

Figures Indicate Bottom of Formations.

clay	150
sand, clay, & shale	685
shale & shells	1375
sand & shale	1760
shale & lime	2190
shale	2390
shale & lime	2485
lime	2660
lime, anhydrite	2770
lime, anhydrite	2780
Total Depth	

Tops:	
Herington	2618
Upper Krider	2644
Lower Krider	2676
Winfield	2732

Perf:
36 shots 2610-16
48 " 2620-28
84 " 2646-60
120 " 2674-2704
80 " 2730-38

S.I.P. 420.5#