

State Geological Survey KANSAS DRILLERS LOG, BRANCH WICHITA

API No. 15 — 175 — 20283
County Number

Operator

Cities Service Oil Company

Address

3545 N.W. 58th Street, Oklahoma City, Oklahoma 73112

Well No.

2

Lease Name

Shives "A"

Footage Location

1420

feet from (N) line

1320

feet from (E) line of NE/4

Principal Contractor

Lohmann-Johnson

Geologist

Spud Date

4-6-76

Total Depth

6461'

P.B.T.D.

Date Completed

4-20-76


Oil Purchaser

S. 18 T. 34S R. 33 W

Loc. 1420' ENL, 1320' EEL of NE/

County Seward

640 Acres
N R33W



T
34
S

Locate well correctly

Elev.: Gr. 2880'

DF 2888' KB 2889'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	24# 28.55#	1605'	Class H	750	Cmt. w/700 sx Howco Lite w/2% CaCl
		followed by	200 sx	Class H w/3% CaCl.	Cement circulated:	150 sx.	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
-----	-----	-----	-----	-----	-----
TUBING RECORD					
Size	Setting depth	Packer set at			
-----	-----	-----	-----	-----	-----

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
N/A	N/A

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
Dry Hole - No Test Conducted.					
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	----- bbls.	----- MCF	----- bbls.	----- CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		
-----			-----		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

ator

Cities Service Oil Company

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Well No.

2

Lease Name

Shives

Dry Hole

S 18 T 34S R 33 ^{="E"}_W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Soil, Red Bed	0	725	Ran Schlumberger Dual Induction Laterolog & Compensated Formation Density w/Gamma Ray - Caliper Log to 6461'	
Red Bed & Shale	725	1595		
Anhydrite	1595	1614		
Red Bed	1614	1865		
Shale	1865	3140		
Lime & Shale	3140	3375		
Shale	3375	3627		
Lime & Shale	3627	3835		
Shale	3835	4557		
Lime & Shale	4557	4740		
Shale & Lime	4740	4884		
Shale	4884	5025		
Lime	5025	5758		
Shale	5758	6287		
Lime & Shale	6287	6461		
T.D.		6461		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

W. A. Givens
Signature

W. A. Givens

Region Engineering Manager

Title

April 27, 1976

Date