

19-34-33W


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock Wichita, Kansas

Company - CITIES SERVICE OIL CO.
Farm - Gleeson "A" No. 1

SEC. 19 T. 34 R. 33W
SE SE SE NW
100' N. & W. of Center

County. Seward

KANSAS



Total Depth. 2770

Comm. 10-10-50

Comp. 10-16-50

Shot or Treated.

Contractor. Barbour Drlg. Co.

Issued. 6-23-51

CASING:

8 5/8" 720' cem. w/325 sx

5 1/2" 2769' cem. w/700 sx

Elevation. 2883

Production. 15,100,000 gas

Figures Indicate Bottom of Formations.

sand & clay	400
sand, clay & shale	725
red bed	845
shale & shells	1575
lime	1605
shale	1900
shale & lime	2300
lime & anhydrite	2500
lime	2655
lime & anhydrite	2760
lime	2770
Total Depth	

Tops:

Herington	2587
Upper Krider	2621
Lower Krider	2652
Winfield	2706

Perf:

20 shots	2588-92
40 "	2596-2604
70 "	2616-30
140 "	2652-80
80 "	2706-22

R.P. 427.0#