

20-34-33W

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock Wichita, Kansas


Company - CITIES SERVICE OIL CO.
Farm - Stevesson No. 1

SEC. 20 T. 34 R. 33W
SE SE SE NW

100' N. & 100' W. of Center

County. Seward

KANSAS



Total Depth. 2760

Comm. 7-24-50

Comp. 7-31-50

Shut or Treated.

Contractor. Barbour Drlg. Co.

Issued. 6-23-51

CASING:

8 5/8" 680' cem. w/275 sx
5 1/2" 2759' cem. w/700 sx

Elevation. 2863

Production. 10,500,000 gas

Figures Indicate Bottom of Formations.

sand & clay	465
sand & shale	645
red bed	870
lime	920
sand & shale	1580
shale & shells	2255
shale & lime	2505
lime	2760
Total Depth	

Tops:

Herington	2600
Upper Krider	2624
Lower Krider	2655
Winfield	2714

Perf:

20 shots	2590-94
30 "	2600-06
50 "	2624-34
160 "	2656-88
130 "	2710-36

S.I.P. 424.2#