

21-34-33W


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock Wichita, Kansas

Company - CITIES SERVICE OIL CO.
Farm - Bruns No. 1

SEC. 21 T. 34 R. 33W
SE SE SE NW
100' N. & 100' W. of Center

County. Seward

KANSAS



Total Depth. 2765
Comm. 10-8-50 Comp. 10-14-50
Shot or Treated.
Contractor. Barbour Drlg. Co.
Issued. 6-23-51

CASING:

8 5/8" 720' cem. w/300 sx
5 1/2" 2764' cem. w/700 sx

Elevation. 2849

Production. 2,420,000 gas

✓
Figures Indicate Bottom of Formations.

sand & clay	325
shale & sand	660
sand	675
red bed	910
lime & shale	1175
sandy shale & shells	1720
shale, red bed & shells	2005
shale & shells	2350
anhydrite, shale & lime	2450
lime	2530
shale & lime	2595
lime	2765
Total Depth	

Tops:	
Herington	2586
Upper Krider	2624
Lower Krider	2652
Winfield	2706

Perf:
40 shots 2622-30'
160 " 2654-86
30 " 2691-97
2500 gal. 15% Az.
9500 gal.
Squeeze
40 shots 2622-30
140 " 2654-82
60 " 2680-86

S.I.P. 427.7#