

28-34-33W

JRM

KANSAS GEOLOGICAL SURVEY
WICHITA BRANCH

FEB 02 1989

PLUGGING PROGNOSIS

DCS #1-28 BLACK
Section 28-34S-33W
Seward County, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JAN 27 1989

CONSERVATION DIVISION
Wichita, Kansas

WELL DATA

RTD & PBD: 6500' KB & 6459' KB
Casing: 4 1/2", 10.5#, J-55, STC @ 6500' KB w/450 sx
8 5/8", 24#, J-55 STC @ 1576' w/575 sx
TOC: 4 1/2" @ 5500' Est.
Perforations: U. Morrow 6082-86' & 6092-95' (28 holes)
Tubing: 2 3/8", 4.7#, J-55 @ 5990' w/Elder "RDG" packer

PROGNOSIS

1. MIRU Completion Unit. Unseat packer and circulate hole w/mud. TOH. LD tubing and haul into yard. RD Completion Unit.
2. MIRU casing pullers. Set CIBP @ 6050' and dump 2 sx cement on top.
3. Stretch casing to determine freepoint. Attempt cut off of 200'-400' below freepoint. After cutting off casing, LD casing to 2750'. Spot 100 sx Class "H" plug from 2750-2550'. (Covers Chase Series, 50' above & below).
4. Pull casing to 1626' & spot 100 sx Class "H" cement plug 50' in and 50' out of 8 5/8" casing @ 1576' (1626'-1526').
5. Spot 10 sx Class "H" cement plug 4'-40'.
6. Fill rathole and mousehole w/cement, if not already done.
7. Cut off 8 5/8" casing 4' BGL & weld on ID plate as per Kansas Corporation Commission specifications.
8. This procedure has been agreed to by Duane Rankin w/the Kansas Corporation Commission in Dodge City, Kansas.

NOTE: Prior to pumping cement plugs, notify Duane Rankin @ 1-316-225-6760.

Serald R. McKedy
Serald R. McKedy

JRM/sm

28-34-33W

DONALD C. SLAWSON

OIL PRODUCER

905 S. FILLMORE, SUITE 200
P.O. BOX 15290, AMARILLO, TEXAS 79105
(806) 374-5256

Donald C. Slawson Black #1-28
1250 FSL, 1250 FEL Section 28-T34S-R33W
Seward County, Kansas
KB 2834

RECEIVED
STATE CORPORATION COMMISSION

JAN 27 1989

CONSERVATION DIVISION
Wichita, Kansas

Herrington	2600	+ 234
Krider	2626	+ 208
Council Grove	2982	- 148
Heebner	4338	- 1504
Toronto	4358	- 1524
Lansing	4486	- 1652
Marmaton	5191	- 2357
Cherokee	5465	- 2631
Morrow	5828	- 2994
Chester	6102	- 3268
St. Genevieve	6462	- 3628

1084G

12-175-20946