

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,

Wichita, Kansas

28-34-33W


Company- STANOLIND OIL & GAS CO.
Farm- Black G.U. "B" No. 1

SEC. 28 T. 34 R. 33W

CSW 1320 N of SL & 1320 E of
WL SW $\frac{1}{4}$

County Seward

KANSAS



Total Depth. 2693
Comm. 3-26-54
Shot or Treated.
Contractor.
Issued. 12-18-54

Comp. 4-18-54

Elevation. 2810 D.F.

Production. 5,901,000 gas

CASING:

8 5/8" 683 com. w/400 sx.
5 1/2" 2657 com. w/800 sx.

Figures Indicate Bottom of Formations.

surface clay	40
sand, blue shale &	
clay	660
red bed	895
gyp	1047
gyp & shale	1286
shale	1619
shale & anhyd.	1658
anhyd.	1710
anhyd., & shale	2316
shale & lime	2400
lime	2465
lime & anhyd.	2521
lime	2630
lime & dolo.	2673
lime	2693
Total Depth	

Tops:
Herington 2626
Kridler 2693

McCullough perf. w/6 SPF as follows:
Herington 2626-2627, 2638-2645

The Western Co. az: as follows:

Kridler	2/2500 gal. 15%, flushed w/2700 gals. wtr.
Herington	w/2000 " " " 2/650 " "
All zones	w/7000 " 7 1/2% " w/2700 gal. "
" "	w/4000 " " " " " "
" "	w/2000 " " " " " "

Schlumberger ran Gamma Ray & Microlog