

28-34-33W

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock Wichita, Kansas

Company - CITIES SERVICE OIL CO.
Farm - Emrie No. 1


SEC. 28 T. 34 R. 33W

SE SE NE NE

1250' S. 150' W. of NEQ

County Seward

KANSAS



Total Depth. 2755

Comm. 11-25-50

Comp. 12-1-50

Shot or Treated.

Contractor. Barbour Drlg. Co.

Issued. 6-23-51

CASING:

8 5/8" 680' cem. w/325 sx
5 1/2" 2754' cem. w/700 sx

Figures Indicate Bottom of Formations.

Elevation. 2827

Production. 12,500,000 gas

shale & sand	40
clay & sand	300
shale & sand, shells	600
red	875
shale & shells	990
sand, shale, shells	1555
shale & lime	1700
shale & shells	2245
shale & lime	2375
broken lime	2485
lime	2755
Total Depth	

Tops:	
Herington	2598
Upper Krider	2624
Lower Krider	2643
Winfield	2708

Perf:	
50 shots	2598-2608
40 "	2624-30
130 "	2654-80
40 "	2708-14

R.P. 416.7#