

29-34-33W

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
508 East Murdock Wichita, Kansas

Company - CITIES SERVICE OIL CO.  
Farm - Tucker "A" No. 1


SEC. 29 T. 34 R. 33W

SE SE SE NW

100' N. & W. of Center

County. Seward

KANSAS



Total Depth. 2770  
Comm. 10-10-50 Comp. 11-16-50  
Shot or Treated.  
Contractor. Barbour Drlg. Co.  
Issued. 6-23-51

Elevation. 2873

Production. 15,900,000 gas

CASING:

8 5/8" 680' cem. w/325 sx  
5 1/2" 2769' cem. w/700 sx

Figures Indicate Bottom of Formations.

sand & clay	300
shale & shells	535
red shale	685
red bed & sand	965
shale & shells	1570
lime	2145
shale & anhydrite	2315
lime	2405
lime & shale	2653
lime	2735
lime & anhydrite	2770
Total Depth	

Tops:	
Herington	2607
Upper Krider	2641
Lower Krider	2672
Winfield	2726

Perf:	
40 shots	2616-24
40 "	2642-50
150 "	2672-2702
30 "	2708-14
40 "	2724-32

S.I.P. 426.2#