

32-34-33W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- ANADARKO PRODUCTION CO.  
Farm- Liberal "B" No. 1

SEC. 32 T. 34 R. 33W  
NE SW NW

Total Depth. 2721'  
Comm. 6-4-61 Comp. 6-10-61  
Shot or Treated.  
Contractor. Moran Brothers  
Issued. 10-21-61

County Seward  
KANSAS



CASING:  
8 5/8" 727' cem w/400 sx.  
4 1/2" 2720' cem w/75 sx.  
1 1/4" 2698'

Elevation. 2848.32' GL

Production. 926,000 CFG

Figures Indicate Bottom of Formations.

surface sand 63  
sand 612  
red bed 697  
lime 728  
lime 845  
lime & shale 1977  
lime & gypsum 2038  
shale & Anhydrite 2177  
shale & lime 2413  
lime & Anhydrite 2521  
lime 2585  
lime & dolomite 2653  
dolomite 2706  
Lime 2721  
Total Depth

TOPS: SCOUT  
Herington 2610  
Krider 2643

OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING & FRACTURING INFORMATION

Name	From	To	No. of Shots	Gallons Used	Kind Used
Krider	2682	92	20	1000	Mud Acid
				3000	Retarded Acid