

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock,  
Wichita, Kansas

34-34-33W


Company- STANOLIND OIL & GAS CO.  
Farm- Fincham G.O. "A" No. 1

SEC. 34 T. 34 R. 33W

SE SE NW NW  
1250 S of NL & 1250 E of WL

County <sup>N<sup>1</sup>/<sub>4</sub></sup> Seward

KANSAS



Total Depth. 2679 P.B. 2670  
Comm. 7-21-54 Comp. 8-13-54  
Shot or Treated.  
Contractor.  
Issued. 12-18-54

Elevation. 2828 D.F.

Production. 2,466,000 gas

**CASING:**  
8 5/8" 730 com. w/400 sx.  
5 1/2" 2662 com. w/900 sx.

Figures Indicate Bottom of Formations.

surface sand	105
surface sand, blue	
shale	675
red rock	730
red rock, shale	1010
salt, shale	1595
shale, shells	2081
shale, anhyd.	2545
shale, lime, anhyd.	2615
lime	2679
Total Depth P.B. 2670	

Tops:  
Herington 2633  
Kridler 2662

Schlumberger ran Gamma Ray & Microlog.

McCullough Perf. w/6 shots per ft. as follows:  
2637-49.

Chemical Process az: as follows:  
All zones w/2500 gal. 15% acid  
Herington w/2000 " " "  
All zones w/7000 " 7 1/2% "