


4-45W MAP NO. 4-84 SEC. 13-34S-33W
 STATE Kans COUNTY Seward LOC. C NE NW
 OPER. Anadarko Production Co. - Liberal, Ks.
 WELL 3 FARM Eubank "B" FT/FR _____ LINE _____
 POL Condit Field (Multi Pay O&G) ELEV. 2831 GR. 2840 DF 2843 KB _____
 CONT. Moran Brothers Drlg. GEOL. Bob Posey
 CO. _____
 INT. _____
 F.R. 3-3-65 SPUD. 3-9-65 COMP. 4-1-65
 TD. 6423 FM. Ste G PBD. _____
 COMP. _____
 RECORD _____
 8 5/8" @1614 w/850 sx. D&A



Data Inc.

(GR Log)		<u>Q #1 (Chest) 6261-89</u> , R 28' (3' sh & 6'
B/Cim	1646 /1185	1m, 2' sh, 5 1/2' 1m, 3' sh, 2' 1m, 4' sh
Her	2647 / 184	& 2' 1m & sh interbed & 1/2' 1m)
U/Kri	2670 / 161	<u>Q #2 (Chest) 6295-6323</u> , R 28' (6' sd &
L/Kri	2701 / 130	6' brn 1m, sli sdy, 2' sd, 4' 1m & 11'
Winf	2764 / 67	red & gry sh), RTD 6415
CG	3028 - 197	<u>DST #1 (Miss) 6245-6423</u> , Op 15", SI/40",
Tor	4362 -1531	Op 40", R 135' M, ISIP 156#/30", IFP 67#,
Lans	4506 -1675	FFP 156#, FSIP 156#/40"
W	5789 -2958	<u>WLT #1 (Mrw) 6000-02 1/2</u> (two chamber tool),

L/Mrw sd 5985 -3154
 Chest 6015 -3184
 L/Chest
 lmy sd 6300 -3469
 B/Chest
 lmy sd 6318 -3487
 Ste G 6360 -3529
 LTD 6423 -3592

1st chamber op 1/2 hr, R 800 cc wtr, 2nd
 chamber R 400 cc wtr (less than 5% form
 wtr), FSIP 250#/30"
WLT #2 (Chest) 6147 1/2-50, Op 90", No rec
 ISIP less than explosion press, D&A
 (3-25-65) - COMPLETED

112,822

6300
 2821
 3469

LIBERAL ELECTRIC LOG TOPS

2831 GL

Winfield 2762 (+69)

Heebner 4342 (-1511)

Toronto 4362 (-1531)

Lansing 4504 (-1673)

Marmaton 5226 (-2395)

Morrow 5768 (-2937) — 2947

"S-3" 5984 (-3153) 10/26; tst wtr

Chester 6014 (-3183)

Lmy Sand Zone 6300 (³⁴⁶⁹~~-2569~~) 0/18; tst 135' Mud

Ste. Gen 6378 (-3547)

TD 6423 D & A

6300
-2569
3731