

4-288W

MAP NO.

E-84

SEC.

13-34S-33W

STATE Kans

COUNTY

Seward

LOC.

C NE SEOPER. Anadarko Production Co. - Liberal, Ks.

FT/FR

LINE

WELL 4 FARM Eubank "B"

FT/FR


LINE

CONdit Field (Multi Pay O&G) ELEV. 2809 GR. 2816 DF. 2819 KBCONT. Moran Brothers

GEOL.

Bob Posey

CO. INT.

F.R. 3-29-65 SPUD. 3-28-65 COMP. 4-29-65TD. 6374 FM. Ste G PBTD.COMP. RECORD Chest 6276-90 24 1250ACo Flo 273 BO & 2% wtr thru 20/64" choke/25½ hrs8 5/8" @1599 w/900 sx. 4½" @6369 w/130 sx.

Data Inc.

(GR Log)

B/Cim 1635 /1174

Herr 2642 / 167

U/Kri 2666 / 143

Winf 2760 / 49

Tor 4365 -1545

Lans 4478 -1669

Mrw 5774 -2965

Chest 6014 -3205

(cont Below)

DST #1 (Mrw) 5902-6046, Op 45", R 75' M,

ISIP 135#/40", IFP 62#, FFP 62#, FSIP

106#/40", RTD 6370, Log, 4½" @6369 w/

130 sx., Pf 4/6288-90 (Chest), 250A, § 1

ld, Flo 38 BO & 150,000 Cfgpd/2 hrs, Pf

20/6276-86 (Chest), Flo 33 BO & 196,000

Cfgpd/1½ hrs, 1000A, 2 3/8" tbg @6298,

§ ld, Flo 55 1/3 BO & 162,000 Cfgpd/3 hrs,

Flo 69 BO/4 hrs, Flo 20 BO/died, Flo 280

BO/8 hrs, 1" choke, Flo 212 BO/12 hrs,

Ste G 6356 -3547

LTD 6374 -3565

RTD 6370 -3561

25/64" choke, FCP 620#, FIP 180#, Co

Flow 273 CO & 2% BS&W in 25½ hrs, 20/64"choke, DTP 180#, FCPP1100#, Chest 6276-6290 - COMPLETED (4-26-65)

LIBERAL ELECTRIC LOG TOPS

2809 GL

Winfield 2760 (+52)
Heebner 4332 (-1520)
Toronto 4356 (-1544)
Lansing 4488 (-1676)
Marmaton 5192 (-2380)
Morrow 5768 (-2954) ²⁹⁶⁵
"S-3" 5956 (-3144) 12/22; tst mud
Chester 5982 (-3070)
Sand 6256 (-3444) 28/36; ϕ flo 273 BOPD + 8% wtr
Ste. Gen 6358 (-3546)
TD 6374

2809
2965
12/22