

4-44W MAP NO. K84 SEC. 2-34S-33W
 STATE Kans COUNTY Seward LOC. C SW NE

OPER. Anadarko Production Co. - Liberal, Ks. FT/FR _____ LINE _____

WELL 1 FARM Gilmore "B" FT/FR _____ LINE _____

Evalyn Pool Ext (Mrw O&G) ELEV. 2834 GR. 2844 2847 KB

Moran Brothers Drlg. GEOL. Bob Posey

CONT. _____

INT. _____

F.R. 2-16-65 SPUD 2-17-65 COMP. 4-1-65

TD. 6603 FM. Sperg PBTD. _____

Chest sd 6169-91 24 natural

4 Pt Cal OF 6,600,000 Cfgpd, BHP 1954½

8 5/8" @1603 w/850 sx. 4½" @6270 w/150 sx.



Data Inc.

(GR Log)		<u>DST #1 (Mrw) 5719-5809, Op 23", R 30' M,</u>
Herr	2616 / 218	ISIP 124#/30", IFP 79#, FFP 85#, FSIP 93#/ 30"
U/Kri	2636 / 198	
L/Kri	2668 / 166	<u>DST #2 (Chest) 6158-6208, Op 5", GTS/1",</u>
Winf	2734 / 100	Ga 3,114,000 Cfgpd/3", SI/45", Op 30", Ga
U/FR	2792 / 42	5,876,000 Cfgpd/5", Ga 7,116,000 Cfgpd/8",
CG	2990 - 156	Flo mud/10", Ga 7,800,000 Cfgpd/15", Ga
Tor	4326 -1492	8,544,000 Cfgpd/20" & stab, R 1' Cond,
Lans	4455 -1621	ISIP 1964#/45", IFP 1230#, FFP 1536#, FSIP
W	5722 -2888	1964#/45"

B/Mrw sd	5874 -3040	<u>DST #3 (St L) 6350-6440, Op 1 hr, R 10'</u>
B/sd	5898 -3064	M, ISIP 183#/20", IFP 83#, FFP 83#, FSIP
Chest	5898 -3064	83#/20", RTD 6600, Ran Log, 4½" @6270 w/ 150 sx., Pf 4/6169-70, 20/6181-91 (Chest),
Chest sd	6176 -3342	Ga 8,544,000 Cfgpd & 23½ B cond/3 hrs -
B/sd	6194 -3360	SICP 1620#/5", 2 3/8" tbg 6200, 1 hr BD
Ste G	6262 -3428	Ga 3,496,000 Cfgpd thru tbg, 1 hr BD Ga
St L	6354 -3520	8,636,000 Cfgpd thru csg, 45" BD Ga
Sperg	6508 -3674	5,592,000 Cfgpd thru tbg, SICP 1640#,
LTD	6603 -3769	SITP 1640#, BHP 1954½, 4 Pt Cal OF:
RTD	6660	<u>6,600,000 Cfgpd, SITP 1554#, SICP 1536#,</u> <u>Chest 6169-91 - COMPLETED (3-25-65)</u>

LIBERAL ELECTRIC LOG TOPS

2834 GL

Winfield ^{2736 +90}~~2764~~ (+70)
Heebner 4308 (-1474)
Toronto 4326 (-1492)
Lansing 4454 (-1620)
Marmaton 5176 (-2342)
Morrow 5708 (-2874)
"S-3" 5874 (-3040) 5/22
Chester 5916 (-3082)
Sand 6176 (-3342) 16/18; ϕ COF 6,600 MCF
Ste. Gen 6286 (-3452)
St. Louis 6442 (-3608)
TD 6603