


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

Company- CABOT CARBON CORP.
 Farm- Keating-Stephens No. 3

SEC. 2 T. 34 R. 34W
 C NW SE

Total Depth. 6455'
 Comm. 9-13-60 Comp. 10-31-60
 Shot or Treated.
 Contractor. D & M Drilg. Co.
 Issued. 2-18-61

County Seward
 KANSAS



Elevation. 2906' RB

Production. 4,000,000 CFG

CASING:

8 5/8" 2700' cem w/750 sx.
 4 1/2" 6143' cem w/300 sx.

Figures Indicate Bottom of Formations.

sand	635
redbed & shale	1200
sand, shale & redbed	1668
shale & shells	1895
shale	2014
shale & lime	2075
lime	2255
lime & shale	2636
lime	3226
lime & shale	4024
lime	4151
lime & shale	4292
lime	5475
lime & shale	5795
shale	5918
shale & lime	6020
sand, shale & lime	6040
lime	6107
lime & shale	6280
lime	6328
shale & lime	6378
shale	6387
lime	6429
lime & shale	6439
cherty lime	6455
Total Depth	

TOPS:

Winfield	2746
Upper Ft. Riley (scout)	2814
Wreford (scout)	2956
Council Grove	2997
Toronto	4316
Lansing	4438
Marmaton (scout)	5120
Cherokee	5342
Morrow Shale	5760
Morrow Sand	6014-27
Chester-Mississippi	6036
1st Chester sand zone	6300-6322
2nd Chester sand zone	6330-54
3rd Chester sand zone	6380-6444