

KANSAS WELL LOG BUREAU--- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY CABOT CARBON CO.

SEC. 8 T. 34 R. 34W

FARM Ralph M. Heath NO. 1

LOC. SW SW NE  
330 N & E of Center

TOTAL DEPTH 2757'

COMM. 11-20-50


COMP. 1-5-51

SHOT OR TREATED

CONTRACTOR Hills & Hills

ISSUED 5-12-51

COUNTY Seward  
KANSAS



CASING

10 $\frac{3}{4}$ " 719' cem w/325 sxs  
7" 2627' cem w/750 sxs  
5 $\frac{1}{2}$ " lnr. 151'

*2947(m)*  
ELEVATION 2941.86  
*2948 Ind.*  
PRODUCTION 26,560,000gas

FIGURES INDICATE BOTTOM OF FORMATIONS

clay, sand	675
white clay	685
sand, red bed	1670
gyp, red rock	1815
lime, shale	2035
shale, gyp, lime	2145
lime, blue shale	2235
lime, shale	2320
anhydrite	2420
lime, shale	2560
anhydrite	2600
lime	2660
chert, lime	2690
dolomite	2724
shale	2732
lime	2741
dolomite	2757
Total depth	

Tops:  
Herington 2635-2646  
Up. Krider 2652-2660  
L. Krider 2680-2724  
Winfield 2732-2757

Acid 24,000-15%  
Rock Pressure 427.2  
I. P. A. 26,560 MCF/20 min.  
S/G 2655  
Small Inc. 2690-96  
Small Inc. 2702-05  
Inc. 2710-15