

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY CABOT CARBON COMPANY

SEC. 13 T. 34 R. 34W


FARM Lord (Keating) NO. 1

LOC. SE SE NW

330' N & W of center

TOTAL DEPTH 2770
 COMM. 9-26-50 COMP. 10-11-50
 SHOT OR TREATED Acid 20,000
 CONTRACTOR Wagner & Wyant
 ISSUED 3-31-51

COUNTY Seward



CASING
 10 3/4" 689' cem w/300 sx
 7" 2631' cem w/800 sx
 5 1/2" liner 150'

ELEVATION 2900.31 *2900.31*

PRODUCTION IPA 15,136,000 gas

FIGURES INDICATE BOTTOM OF FORMATIONS

clay	0- 130
sand, clay	670
red bed	698
redbed, gyp, shells	970
red bed, gyp	1400
red rock	1605
anhydrite	1625
anhydrite, shale	1760
red rock, shale, anh.	2160
shale, anhydrite	2430
anhydrite	2495
anhydrite, shale	2590
anhydrite, lime	2639
lime	2735
shale	2745
lime	2770
Total Depth	

Tops:
Herr 2626
Upper Li 2654
Laurer Li 2684

Scout Tops:
 Herrington 2625
 Winfield 2745

I.P.N. .250M

S/G - 2667

Rock Pressure: 433.8