


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
 508 East Murdock Wichita, Kansas

Company - CITIES SERVICE OIL CO.
 Farm - Gleeson "B" No. 1

SEC. 24 T. 34 R. 347
 SE SE SE N7

100' N. & W. of Center

County. Seward
 KANSAS



Total Depth. 2770
 Comm. 10-17-50 Comp. 10-23-50
 Shot or Treated.
 Contractor. Barbour Drlg. Co.
 Issued. 6-23-51

Elevation. 2892

Production. 12,100,000 gas

CASING:

8 5/8" 720' cem. w/300 sx
 5 1/2" 2769' cem. w/700 sx

Figures Indicate Bottom of Formations.

clay & sand	690
red bed	805
shale & shells	1570
lime	1625
shale	1960
shale & lime	2200
shale & shells	2300
lime	2340
lime & anhydrite	2545
lime	2690
lime & anhydrite	2770
Total Depth	

Tops:	
Herington	2614
Upper Krider	2630
Lower Krider	2670
Winfield	2722

Perf:	
30 shots	2604-10
40 "	2616-24
40 "	2640-48
150 "	2670-2700
40 "	2706-14
30 "	2722-28
40 "	2732-40

R.P. 407.9#