

TYPE

AFFIDAVIT OF COMPLETION FORM

SIDE ONE

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ~~thirty (30)~~ days after the completion of a well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # Pending EXPIRATION DATE _____

OPERATOR Anadarko Production Company API NO. 15-175-20,642

ADDRESS Box 351 COUNTY Seward

Liberal, Kansas 67901 FIELD Wideawake

** CONTACT PERSON Paul Gatlin PROD. FORMATION Chester

PHONE 316-624 6253

PURCHASER To be determined LEASE Gammell "A"

ADDRESS _____ WELL NO. 1

WELL LOCATION C SW NE

DRILLING Johnson Drilling Company, Inc. 1980 Ft. from North Line and

CONTRACTOR 3535 NW 58th Street, Suite 710 1980 Ft. from East Line of

ADDRESS Oklahoma City, Oklahoma 73112 the NE (Qtr.) SEC 29 TWP 34S RGE 34W.

PLUGGING _____ WELL PLAT _____ (Office

CONTRACTOR _____ Use Only)

ADDRESS _____ KCC _____

KGS ☒

SWD/REP _____

PLG. _____

TOTAL DEPTH 6638 PBTD 6549

SPUD DATE 7/2/82 DATE COMPLETED 7/23/82

ELEV: GR 1934 DF 2942 KB 2944

DRILLED WITH ~~(CABLE)~~ (ROTARY) ~~(XXX)~~ TOOLS.

POCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE _____

Amount of surface pipe set and cemented 1642 DV Tool Used? No

THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Gas, Shut-in Gas, Dry, Disposal, Injection, Temporarily Abandoned, OWWO. Other _____

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

A F F I D A V I T

G. B. Smith, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

G. B. Smith

OPERATOR, Anadarko Production Co. LEASE Gammell "A" #1 SEC. 29 TWP. 34S RGE. 34W

WELL IN WELL INFORMATION AS REQUIRED:

WELL NO.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Surface, Clay & Sand	0'	260'		
Sand & Redbed	260'	657'		
Redbed, Shale, & Sand	657'	1641'		
Anhydrite	1641'	1651'		
Shale	1651'	2493'		
Lime & Shale	2493'	6638'		

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used				Depth interval treated	
A/w 3000 gal 15% MSR 150				6212-28 6246-54	
Date of first production SI for Pipeline		Producing method (flowing, pumping, gas lift, etc.) Flowing		Gravity	
Estimated Production -I.P.	Oil bbls.	Gas 734 MCFD	Water %	Gas-oil ratio bbls.	CFPB
Disposition of gas (vented, used on lease or sold) To be sold			Perforations 6212-28, 6246-54		

Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4	8-5/8	24	1642	Pozmix Common	600 200	4% Gel 3% CaCl
Production	7-7/8	4-1/2	10.5	6600	Litewate Pozmix	75 275	.75% CFR ₂ SS .05% CFR ₂

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
TUBING RECORD			2	.46	6212-28 6246-54
Size 2-3/8	Setting depth 6178	Packer set at			

JOHNSON *Drilling Company, Inc.*



OFFICES IN
EVANSVILLE, INDIANA
TEL. (812) 424-8291
OKLAHOMA CITY, OKLAHOMA
TEL. (405) 943-7667
LIBERAL, KANSAS
TEL. (316) 624-7731

REPLY TO:

3535 N. W. 58th - Suite 710
Oklahoma City, Oklahoma 73112

July 21, 1982

ANADARKO PRODUCTION COMPANY
P.O. BOX 351
LIBERAL, KANSAS 67901

ATTN: PAUL GATLIN

DRILLERS LOG for:

GAMMELL "A" # 1

0' - 260'
260' - 657'
657' - 1641'
1641' - 1651'
1651' - 2493'
2493' - 6638'

Surface, Clay, & Sand
Sand & Redbed
Redbed, Shale, & Sand
Anhydrite
Shale
Line & Shale

JOHNSON DRILLING COMPANY, INC.

Signed by

Claude D. Moore, Manager

STATE OF OKLAHOMA:

COUNTY OF OKLAHOMA:

Subscribed and sworn to before me this 21st day of July, 1982.

Notary Public

My Commission Expires:

October 24, 1984