


90193

1-67W MAP NO. 83 SEC. 32-34S-34W
 STATE Kans. COUNTY Seward LOC. C NW SE
 OPER. W. J. Coppinger, Wichita, Kansas FT/FR _____ LINE _____
 WELL #1 FARM Courtney FT/FR _____ LINE _____
 COOL Wide Awake, Ext. ELEV. _____ GR. 2924 DF 2927 KB _____
 O. INT. Mahoney Drlg. Co. GEOL. _____
 F.R. 10-18-63 SPUD 10-20-63 COMP. 1-7-64
 TD 6735 FM. St. L. PBTD. _____
 COMP. RECORD 8-5/8" @1398' w/800 Sx. D&A _____



Data Inc.

DF Log Tops:

Chase <i>Her</i>	2616	+ 308	Mar	5264	-2340
CG	2984	- 60	Cher	5496	-2572
Adm	3322	- 398	Atok	5666	-2742
Wab	3454	- 530	Mrw	5838	-2914
Shaw	3813	- 889	Ches	6151	-3227
Hb	4278	-1354	St. G	6504	-3580
Tor	4330	-1406	St. L	6591	-3667
LKC	4427	-1503	LTD	6735	-3811

DST #1(Tor)4341-94, Op 1 hr, R 75' GCM, 75' M, ISIP 1178#/30'.

IFP 37#, FFP 64#, FSIP 1160#/30'.

DST #2(St. L.)6625-58, Op 1 hr, R 180' GCM w/some free oil, ISIP 1981#/30', IFP 50#, FFP 100#, FSIP 1615#/30'.

DST #3(St.L)6662-92, Op 1 hr, R 30' V sli GCM, w/rnbw SO, ISIP 2147#/60', IFP 33#, FFP 33#, FSIP 1948#/60'.

RTD 6735', Note: No poro in St. Gen. SJ Log, 4 1/2" @6733' w/100Sx.

Pf 8/6630-32, (St. L)\$ dry nat. 300A, \$ 1d & \$ dry. 20/6636-

41(St. L)\$ 21 GWPH w/SO&G/NT, 3000A, \$ 1d, \$ 21 GFPH (wtr w/ SO&G)/36 hrs. D&A 12-23-63, COMPLETED

LIBERAL ELECTRIC LOG TOPS

2926 KB

Winfield 2734 (+192)

Heebner 4310 (-1384)

Toronto 4328 (-1402) tst GCM

Lansing 4438 (-1512)

Marmaton 5154 (-2228)

Morrow 5840 (-2914)

No Sands

Chester 6160 (-3234)

Sand Zone 6440 (-3514) no por (?no sand)

Ste. Gen 6504 (-3578)

St. Louis 6590 (-3664) \$ 21 GF1PH/36 hrs. + SO&G

TD 6735