

31-34-35W

KANSAS GEOLOGICAL SOCIETY  
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
KANSAS GEOLOGICAL SOCIETY BUILDING  
508 EAST MURDOCK - WICHITA, KANSAS


COMPANY **SUNRAY DX & CITIES SERVICE OIL**  
FARM **Stalcup "E"** NO. 1

SEC. 31 T. 34 R. 35W  
LOC. C SE SW

TOTAL DEPTH 6625  
COMM. 3-25-66  
SHOT OR TREATED  
CONTRACTOR **Unit Drlg.**  
ISSUED 8-6-66

COMP. 4-7-66

COUNTY **Stevens**



CASING

20	10		
15	8 5/8"	@ 1745'	w/700 SX.
12	6		
13	4 1/2"	@ 6623'	w/200 SX.

ELEVATION 3027' KB

PRODUCTION 4 PT COF  
800 MCFG

FIGURES INDICATE BOTTOM OF FORMATIONS

0 -	375	Sand
375 -	940	Sand & red Shale
940 -	1580	Sand, R. B., shale & anhydrite
1580 -	1745	Red Bed & lime
1745 -	1783	Anhydrite & shale
1783 -	2308	Anhydrite
2308 -	2737	Anhydrite & shale
2737 -	2970	Anhydrite & dolomite
2970 -	3518	Dolomite
3518 -	3740	Lime, shale & chalky streaks
3740 -	3988	Lime, shale & chalk
3988 -	4980	Lime & shale
4980 -	5135	Lime with shale streaks
5135 -	6006	Lime & shale
6006 -	6437	Lime, shale & sand
6437 -	6625	Lime & shale
	6625	Total Depth

TOPS: SCOUT

Heebner	4325
Toronto	4350
Lansing	4470
Drum	4920
Base Kansas C.	5120
Marnaton	5210

CASING & CEMENTING RECORD

3-26-66 Ran 53 jts. of 8 5/8", 24#, J55, 8RT, ST&C casing, total of 1745' set @ 1745' K.B. Cemented with 600 sks. poz, 4% Gel & 2% CC and 100 sks. common with 3% HA5. Plug down @ 4:30 A.M.

4-7-66 Ran 204 jts. of 4 1/2", J55, 8RT, ST&C Youngstown casing, 29 jts. of 10 1/2" on bottom, 172 jts. of 9 1/2" in the middle & 3 jts. of 10 1/2" on top. Total of 6627.69' set @ 6623' K.B. Cemented with 200 sks. salt saturated poz, 1/2 of 1% CFR2. Plug down @ 10:00 A.M.

Base Ft. Scott	5460
Atoka	5632
Base Atoka	5920
Purdy Sand	5930
Morrow	5936
Keyes	6250
Morrow Sand	6320
Chest	6352
Chest Sand	6568
St. Geneieva	6594

RECEIVED  
 KANSAS GEOLOGICAL SOCIETY  
 WICHITA, KANSAS  
 8-10-66

COPY