

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY

Wichita, Kansas

8- 34 - 35W


Company - CITIES SERVICE GAS CO.
 Farm - Barrett No. 1

SEC. 8 T. 34 R. 35W
 SE SE NW

Total Depth. 2814
 Comm. 7-24-48 Comp. 8-14-48
 Shot or Treated. 19,000 gals.
 Contractor. J. R. McGill
 Issued. 12-24-49

County. Stevens

KANSAS

Elevation. 3025 feet

Production. 25,054,000 CFG

CASING:

10" set @ 610' w/300 sx.
 7" set @ 2676' w/1000 sx.
 5" OD liner 160'

Figures Indicate Bottom of Formations.

Surface soil	5
Sand	40
Sand & Anhydrite	410
Shale & sand	670
Shale &	810
Sand & shale	1020
Anhydrite	1070
Gyp & shale	1180
Sand	1268
Sand & shale	1410
Sand & shale & gyp	1500
Sand & shale	1650
Gyp & red rock	1750
Gyp, shale & Anhy.	1995
Anhydrite & shale	2595
Anhy. shale & ls.	
shells	2680
Anhydrite & shale	2688
Lime	2760
Shale	2768
Lime	2813
Shale	2814

Total Depth

First gas @ 2691
 Increase @ 2730-33
 656 M @ 2748
 865 M @ 2752
 927 M @ 2754 - Acidized Krider formation