

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock Wichita, Kansas

10-34-35W

Company - CITIES SERVICE OIL CO.
Farm - Skinner "B" No. 1


SEC. 10 T. 34 R. 35W

NE NE NE SW

100' S. & 100' W. of Center

County. Stevens

KANSAS



Total Depth. 2794

Comm. 10-30-49

Comp. 11-12-49

Shot or Treated.

Contractor. J. R. McGill Drlg. Co.

Issued. 6-23-51

CASING:

10 3/4" 794' cem. w/325 sx

7" 2696' cem. w/1000 sx

5 1/2" liner @ 2794' ?

Elevation. 2991

Production. 23,900,000 gas

Figures Indicate Bottom of Formations.

surface	8
sand, clay & gravel	765
red sand	790
red bed	823
red bed, sand & gyp	1380
red bed, gyp & salt	1670
anhydrite & gyp	1760
red bed, shale & gyp	1880
shale & gyp shells	2020
gyp, red rock & shale	2130
red rock & shale	2200
shale, gyp & anhydrite	2377
anhydrite & shale	2465
anhydrite	2695
dolomite	2700
2700 rotary T.D. = 2697 SLM	
dolomite (first gas @ 2715)	2738
lime	2756
red shale	2763
lime	2794
Total Depth	

Tops:

Herington	2665
Upper Krider	2693
Winfield	2763

11-12-49 at T.D. 2759 Acidized
with 2000 gals. 15% Acid.
2,500,000 gas
Deepened 2759-2794'

11-13-49 Acidized
5,400,000 gas

11-14-49 Acidized 15,000 gals.
15% Acid. 7,050,000 gas

11-16-49 Acidized 6000 gals.
5% Acid