

13-34-35W


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock Wichita, Kansas

Company - CITIES SERVICE OIL CO.
Farm - Cole No. 1

SEC. 13 T. 34 R. 35W
NE NE NE SW
100' S. & 100' W. of Center

County. Stevens

KANSAS



Total Depth. 2820
Comm. 1-22-50 Comp. 1-27-50
Shot or Treated.
Contractor. Corbett & Barbour Drlg. Co.
Issued. 6-23-51

CASING:

8 5/8" 812' cem. w/325 sx
5 1/2" 2819' cem. w/800 sx

Elevation. 2978

Production. 20,800,000 gas

Figures Indicate Bottom of Formations.

sand & shale	330
sand & clay	760
red bed	970
shale & sand	1695
sand & shale	2000
shale & lime	2390
shale & anhydrite	2390
lime	2825
2825 Rot. T.D.=2820 Corr. to ground	
Total depth	

Tops:	
Herington	2654
Upper Krider	2685
Lower Krider	2714
Winfield	2766

Perf:	
50 shots	2662-72
40 "	2686-94
190 "	2716-54
40 "	2766-74
90 "	2778-96

S.I.P. 420.1#