

14-34-35W

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock Wichita, Kansas


Company - CITIES SERVICE OIL CO.
Farm - Clodfelter No. 1

SEC. 14 T. 34 R. 35W
NE NE NE SW
100' S. & 100' W. of Center

Total Depth. 2820
Comm. 12-28-49 Comp. 1-3-50
Shot or Treated.
Contractor. Corbett & Barbour Drlg. Co.
Issued. 6-23-51

County. Stevens

KANSAS



Elevation. 2981

Production. 20,700,000 gas

CASING:

8 5/8" 805' cem. w/325 sx
5 1/2" 2814' cem. w/700 sx

Figures indicate Bottom of Formations.

sand & shale	750
red bed	900
shale & shells	1750
shale & lime	1980
shells & shale	2240
shale & lime	2505
lime & shale	2588
lime	2670
lime & shale	2820
2820 Rot. T.D.=2815 Corr. to ground	
Total Depth	

Tops:	
Herington	2653
Upper Krider	2683
Lower Krider	2708
Winfield	2762

Perf:
50 shots 2662-72
2500 Acid
40 shots 2684-92
190 shots 2714-52
160 shots 2764-96

S.I.P. 414.1#