

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY

500 E. Murdock,

Wichita, Kansas

15-34-35W

Company. CITIES SERVICE GAS CO.

Farm. Skinner

No. 1

SEC. 15
SE SE NW

T. 34

R. 35W

Total Depth. 2834

Comm. 6-15-49

Comp. 6-29-49


Shot or Treated. acid

Contractor. J. R. McGill

Issued. 9-24-49

County. Stevens

KANSAS

Elevation. 3015 *ft*

Production. 26,041,000 gas.

CASING:

10 3/4" OD 764'3" cem w/300 sx. Circ.

7" OD 2692'10" cem. w/1000 sx. Circ.

5 1/2" liner 191'4" Top 2643' Bottom 2834

Figures indicate Bottom of Formations.

sand & clay	750
red bed & shale	853
red bed & sand	1025
GYP	1075
sand	1560
GYP & sand	1600
red bed & sand	1700
GYP & anhyd.	1850
anhyd., GYP & shale	1960
GYP & shale	2050
anhyd., GYP, & shale	2115
shale, GYP & anhyd.	2240
anhyd. & shale	2440
shale & anhyd.	2499
anhyd. & lime	2569
lime & shale	2627
shale & lime	2720
lime	2782
shale	2785
shale blue	2787
shale red	2797
lime	2830
shale blue	2834
Total Depth	

Gas Record

First show of gas 2700

Increase gas 2745

Gauged 656 M 2757

" 1,036 M 2782

" 1,311 M 2810-15

" 1,854 M 2815-20

" 2,370 M 2820-25

Acidified w/19,000 gals. of 15% acid in
four stages.