

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock,

Wichita, Kansas


17-34-35W

Company- CITIES SERVICE GAS CO.  
Farm- DeCamp No. 1

SEC. 17 T. 34 R. 35W  
NE NE SW

Total Depth. 2835'  
Comm. 9-13-48 Comp. 10-2-48  
Shot or Treated.  
Contractor. J. R. McGill  
Issued. 5-31-58

County Stevens  
KANSAS



CASING:  
10 3/4" 692' cem w/300 sx.  
7" 2690' cem w/1000 sx.  
5 1/2" 2935'

Elevation. 3052'

Production. 23,019,000 MCF  
RP 396.5#

Figures indicate Bottom of Formations.

|                      |      |
|----------------------|------|
| sand                 | 85   |
| sand & gravel        | 430  |
| sticky red shale     | 540  |
| shale, gumbo & sand  | 680  |
| gumbo                | 765  |
| shale & red bed      | 818  |
| red bed              | 880  |
| red bed, shale & gyp | 1180 |
| sand                 | 1400 |
| shale & sand         | 1550 |
| shale & lime         | 1615 |
| Anhydrite & shale    | 1930 |
| shale & anhydrite    | 2030 |
| anhydrite & shale    | 2305 |
| anhydrite & lime     | 2354 |
| anhydrite & shale    | 2440 |
| anhydrite & lime     | 2494 |
| lime & shale         | 2557 |
| lime                 | 2660 |
| lime & shale         | 2700 |
| lime                 | 2715 |
| grey lime            | 2784 |
| lime                 | 2789 |
| pink shale           | 2790 |
| broken shale         | 2794 |
| lime                 | 2834 |
| blue shale           | 2835 |
| Total Depth          |      |

GAS RECORD:

|              |         |
|--------------|---------|
| First Gas    | 2720    |
| Increase Gas | 2745-65 |
| 1,226 M      | 2775    |
| 1,967 M      | 2830    |