


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - CITIES SERVICE GAS COMPANY
Farm - Anderson No. 1

18-34-35W
SEC. 18 T. 34 R. 35W
NW NW SE
150' SE of center of Sec.

Total Depth. 2807
Comm. 12-8-48 Comp. 12-22-48
Shot or Treated. acid w/19000 gals. 15% acid in 4 stages.
Contractor. J. R. McGill, Amarillo, Texas
Issued. 3-5-49

County. Stevens
KANSAS



CASING:
10 3/4" 716'2", cem w/300 sx., Circulated
7"OD 2663'11", cem w/1000 sx. Circulated
5 1/2"OD 2807'

Elevation. 3031' Ind.

Init. Production. 22,019,000 gas

Figures Indicate Bottom of Formations.

surface	400
sand, clay	575
sand, gravel	625
sand, clay	700
red bed	815
redbed, sand	1030
gyp	1152
sand, shale	1685
anhydrite, shale	1975
shale, lime	2041
shale, gyp	2235
lime, shale	2315
lime	2388
shale, lime	2455
lime	2670
lime brkn	2718
lime	2756
shale	2760
shale red	2766
lime	2805
shale	2807
total depth	

GAS RECORD

First gas	2687
656 M	2730
1136 M	2745
927 M	2793
Increase Gas	2794-2800
1725 M	2803