


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

21-34-35W
SEC. 21 T. 34 R. 35W
SW SW NE

Company- CITIES SERVICE GAS CO.
Farm- Stockstill No. 1

Total Depth. 2823'
Comm. 5-27-49 Comp. 6-10-49
Shot or Treated.
Contractor. J. R. McGill
Issued. 6-21-58

County Stevens
KANSAS



CASING:
10 3/4" 771' cem w/300 sx.
7" 2694'9" cem w/1000 sx.
5 1/2" 162'7"

Elevation. 3012'

Production. 19,401,000 MCF
RP 402#

Figures Indicate Bottom of Formations.

sand	40
sand & shale	222
sand & clay	750
blue shale & red bed	805
red bed	950
gyp & sand	1270
sand & gyp	1400
red bed	1722
red bed & anhydrite	1815
red bed & gyp	1970
anhydrite & red bed	2095
anhydrite & shale	2650
lime	2747
shale	2750
lime	2774
blue shale	2780
red rock	2785
lime	2821
blue shale	2823
Total Depth	

GAS RECORD:

First Show of gas	2702	Gauged	2,070 M	2795
Gauged 133 M	2761	"	2,020 M	2800
" 1,311 M	2766	"	1,915 M	2805
" 1,391 M	2770	"	2,070 M	2810
" 1,391 M	2776	"	3,358 M	2815
Acidized at 2776'. Gauged		"	2,700 M	2820
2,020 M after acid		"	2,778 M	2823 TD

Acidized with 19,000 gallons of 15% acid in four stages.