

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 E. Murdock,

Wichita, Kansas

22-34-35W

Company - CITIES SERVICE GAS CO.
Farm - Bonsall No. 1SEC. 22 T. 34 R. 35W
NE NE SW

Total Depth. 2805 2805

Comm. 6-23-49

Comp. 7-8-49


Shot or Treated. acid

Contractor. J. R. McGill

Issued. 9-24-49

County. Stevens

KANSAS



Elevation. 2988' and

Production. 24,759,000 gas

CASING:

10 3/4" OD 746' cem. w/300 sx. Circ.
 7" OD 2660' cem. w/1000 sx. Circ.
 5 1/2" liner OD 161' Top 2644' Bottom 2805'

Figures Indicate Bottom of Formations.

sand & clay-	710
shale & red bed	823
red bed & sand	1025
gyp	1080
sand	1450
sand	1450
red bed & sand	1645
gyp & sand	1675
shale, gyp & anhyd.	1915
anhyd. & shale	1990
gyp & shale	2085
anhyd. & shale	2105
anhyd.	2115
shale & gyp	2365
shale, gyp & anhyd.	2440
shale, anhyd. & lime	2504
anhyd. & lime	2585
lime & shale	2673
lime	2751
shale blue	2757
shale red	2761
lime	2802
shale red	2805
Total Depth	

First show of gas	2682
Increase gas	2720
" "	2730-36
Gauged 1,800 M	2745
" 1,854 M	2753
" 2,972 M	2767-70
" 4,059 M	2800-02

Acidized w/19,000 gals of 15% acid in
four stages.