

24-34-35W


WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
508 East Murdock Wichita, Kansas

Company - CITIES SERVICE OIL CO.
Farm - Hudkins No. 1

SEC. 24 T. 34 R. 35W
SE SE SE NW

100' N. & 100' W. of Center

County. Stevens
KANSAS



Total Depth. 2830 2825 Corr. to gr.
Comm. 1-13-50 Comp. 1-19-50
Shot or Treated.
Contractor. Corbett & Barbour Drlg. Co.
Issued. 7-7-51

CASING:

8 5/8" 760' cem. w/325 sx
5 1/2" 2824' cem. w/700 sx

Elevation. 2977

Production. 17,800,000 gas

Figures Indicate Bottom of Formations.

sand & clay	730
red bed	760
red bed & shale	1700
lime & shale	1790
shale & lime	1955
shale & shells	2215
shale & lime	2385
lime	2560
lime & shale	2650
lime	2830

2830 Rotary T.D. = 2825 Corr.
to ground.
Total Depth

Tops:	
Herington	2650
Upper Krider	2684
Lower Krider	2710
Winfield	2770

Perf:
20 shots 2654-58
40 " 2662-70
50 " 2686-96
150 " 2718-48
20 " 2752-56
20 " 2770-74
140 " 2778-2806

RP 426.7#