

33-34-35W

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


Company. CITIES SERVICE GAS CO.
Farm. Fred C. Koch No. 1

SEC. 33 T. 34 R. 35W
NWc SE
150' f Con Soc

Total Depth. 2858'
Comm. 10-24-44
Shot or Treated.
Contractor. R. W. Rino
Issued. 3-1-47

Comp. 11-24-44

County. Stevens
KANSAS



Elevation. 2993 ft

Production. 5,669,000 Gas
Rock Pres. 434#

CASING:

0 3/4" 671' 3" cem.w/ 300 sx.
7" 2701' 11" cem w/ 1000 sx.
5 1/2" 2689' - 2814' (Liner)

Figures Indicate Bottom of Formations.

sand & clay	0-370
clay & gyp	545
clay & red bed	675
red bed	1340
red bed & gyp	1645
anhydrite	1700
red bed & gyp	2330
red bed, gyp & shalo	2405
shalo & limo	2611
limo	2757
shalo	2765
limo	2812
shalo	2821
lime	2858
Total Depth	

Gas Record:

First show	2720
924 M. 924	2735
1,470 M. 1,470	2750
1,134 M.	2775
2,058 M. 2,058	2795
2,520 M.	2800
2,730 M.	2805
2,898 M. (Maximum gaugo)	2809
2,604 M.	2812

Plug Back Record:

Original total Depth and base of the
Ft. Riley 2858'
Plugged back to 2835' with 800# wool.
Plugged back to 2814' with Quickard cem.
Drilled out cement 2814' to 2818'
Ran 37 1/2 gal. plastic in four stages
and obtained no fill up.
Cleaned out hole to 2818'; ran 15
gal. plastic one stage no fill up.
Ran 8' gravel 2818 to 2810.
Drilled out gravel to 2813'
Ran 15 gal. plastic one stage.
Filled up 2813' to 2810'