


35-34-35W

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock Wichita, Kansas

Company - CITIES SERVICE OIL CO.
Farm - Rennick No. 1

SEC. 35 T. 34 R. 35W
100' S. & 100' W
of center
NE NE NE SW

County. Stevens
KANSAS



Total Depth. 2830=2825 corr. to ground
Comm. 1-1-50 Comp. 1-8-50
Shot or Treated.
Contractor. Corbett & Barbour Drlg. Co.
Issued. 7-7-51

CASING:

8 5/8" 800 cem w/325 sxs.
5 1/2" 2824 cem w/700 sxs.

Elevation. 2966

Production. 21,800,000 gas

Figures Indicate Bottom of Formations.

sand, clay	500
shale	745
red bed	800
red bed, sand	1350
red rock, anhydrite,	
lime	1750
shale, lime	1950
shale, anhydrite	2065
shale, lime	2350
shale, anhydrite	2455
lime, shale	2590
anhydrite, lime	2645
lime	2830RTD
2830 R.T.D.=2825 Corr. to	
ground	
Total Depth	
Tops:	
Herington	2654
Upper Krider	2678
Lower Krider	2706
Winfield	2762
Upper Ft. Riley	2820

Perforated:
40 shots 2654-62
50 shots 2676-86
210 shots 2708-50
30 shots 2762-68
120 shots 2774-98

SIP 419.6#