


100' S. & 100' W. of Center

36-34-35W
County. Stevens

KANSAS



Total Depth. 2784
Comm. 10-19-49 Comp. 11-6-49
Shot or Treated. 24000 gals.
Contractor. J. R. McGill Drlg. Co.
Issued. 7-7-51

CASING:

10 3/4" 800' cem w/325 sxs. 128' of 5 1/2" liner
7" 2676' cem w/1000 sxs. at 2784'

Figures Indicate Bottom of Formations.

Elevation. 2957

Production. 24,700,000 gas

soil	25
sand, clay	150
sand, gravel	422
sand, gravel, red bed	780
sand	790
red bed	820
sand, gyp	1365
gyp, redbed	1415
gyp, sand, anhydrite	1719
anhydrite, sand	1760
shale, gyp	1895
sand, gyp, shells	2000
shale, gyp	2173
shale, anhydrite	2275
broken lime	2380
gyp, shale, broken	
lime	2450
shale, anhydrite	2480
shale, anhydrite, lime	2510
shale, lime	2530
broken lime	2579
lime	2623
broken lime	2657
anhydrite, lime, shale	2680
2680 RTD=2678 SLM	
lime	2743
red shale	2747
lime	2784
Total depth	

Tops:

Herington	2646
Upper Krider	2675
Lower Krider	2697
Winfield	2753

Deepened 2743-2784

11-4-49 Acidized 2743 w/2000
gals. 15% acid

11-6-49 Acidized 2678-2784 w/5000
gals. 15% acid.

11-8-49 Acidized 15,000 gals.
15% acid.

11-10-49 Acidized 6000 gals.
5% acid.

R. P. 413.4#